

**GOVERNMENT OF INDIA
MINISTRY OF RAILWAYS
LOK SABHA
UNSTARRED QUESTION NO. 4095
TO BE ANSWERED ON 12.08.2026**

INSTALLATION OF KAVACH ON HIGH-DENSITY RAILWAY ROUTES

4095. DR. BHOLA SINGH:

Will the Minister of RAILWAYS be pleased to state:

- (a) the details of the progress made in deployment of Kavach 4.0 across the country including route kilometres and locomotives covered, zone-wise;**
- (b) the details of railway routes passing through Bulandshahr Lok Sabha Constituency identified/covered for installation of Kavach;**
- (c) whether the Government proposes to extend Kavach to other railway sections serving Bulandshahr and adjoining districts;**
- (d) if so, the details and timeline fixed thereof; and**
- (e) the measures taken/being taken by the Government to expedite Kavach deployment on high-density and high-traffic railway routes?**

ANSWER

**MINISTER OF RAILWAYS, INFORMATION & BROADCASTING AND
ELECTRONICS & INFORMATION TECHNOLOGY**

(SHRI ASHWINI VAISHNAW)

(a) to (e):

- 1. Kavach is an indigenously developed Automatic Train Protection (ATP) system. Kavach is a highly technology intensive system, which requires safety certification of highest order (SIL-4).**
- 2. Kavach aids the Loco Pilot in running of trains within specified speed limits by automatic application of brakes in case Loco Pilot fails to do so and also helps the trains to run safely during inclement weather.**
- 3. The first field trials on the passenger trains were started in February 2016. Based on the experience gained and Independent Safety**

Assessment of the system by Independent Safety Assessor (ISA), three firms were approved in 2018-19, for supply of Kavach Ver 3.2.

- 4. Kavach was adopted as National ATP system in July, 2020.**
- 5. Implementation of Kavach System involves following Key Activities:**
 - a. Installation of Station Kavach at each and every station, block section.**
 - b. Installation of RFID Tags throughout the track length.**
 - c. Installation of telecom Towers throughout the section.**
 - d. Laying of Optical Fibre Cable along the track.**
 - e. Provision of Loco Kavach on each and every Locomotive running on Indian Railways.**
- 6. Based on deployment of Kavach version 3.2 on 1,465 RKm on South Central Railway and experience gained, further improvements were made. Finally, Kavach specification version 4.0 was approved by RDSO on 16.07.2024.**
- 7. Kavach version 4.0 covers all the major features required for the diverse railway network. This is a significant milestone in safety for Indian Railways. Within a short period, IR has developed, tested and started deploying Automatic Train Protection System.**
- 8. Major improvement in Version 4.0 includes increased Location Accuracy, Improved Information of Signal Aspects in bigger yards, Station to Station Kavach interface on OFC and Direct Interface to existing Electronic Interlocking System. With these improvements, Kavach Ver.4.0. is planned for large scale deployment over Indian Railways.**
- 9. After extensive and elaborate trials, Kavach Version 4.0 has been successfully commissioned on 2,633 Route Kilometres as on 31.07.26,**

covering the high density Delhi- Mumbai and Delhi-Howrah routes as below:

SN	Section	Progress (Route Km)
(1)	Delhi-Mumbai route: 1,423 Rkm	
i	Tilak Bridge - Junction cabin – Palwal – Mathura –Kota-Nagda-Ratlam–Vadodara-Virar section	1,327
ii	Vadodara – Ahmedabad section	96
(2)	Delhi – Howrah route: 1,210 Rkm	
i	Chippyana - Tundla - Kanpur - Subedarganj section	563
ii	Kanpur – Lucknow section	71
iii	Mirzapur - DDU (Excluding) section	64
iv	DDU(FOC)-Bhabua Road section	50
v	Sasaram - Phesar section	43
vi	Gaya -Sarmatarn- Nimiaghat section	159
vii	Chota Ambana - Bardhaman – Howrah section	260

10. In addition, track side Kavach implementation work has been taken up on 21,794 RKM covering all GQ,GD,HDN and identified sections of Indian Railways. Further, Kavach work is planned for Aligarh – Chandausi & Hapur - Khurja sections passing through Bulandshahr Lok Sabha constituency.

11. The total Progress of key items of Kavach on Indian Railway sections are as under:-

SN	Item	Progress
i	Laying of Optical Fibre Cable	11,547 Km
ii	Installation of Telecom Towers	1,721 Nos.
iii	Station Data Centre	1,009 station
iv	Installation of Track side equipment	7,726 RKm
v	Provision of Kavach in Loco	6,290 Nos.

12. In addition, work for installation of Kavach in 7,190 Locomotives and 1,200 EMU/MEMU has been taken up.

13. Specialized training programmes on Kavach are being conducted at centralized training institutes of Indian Railways to impart training to all concerned officials. By now more than 94,000 technicians, operators and engineers have been trained on Kavach technology. This includes about 57,000 Loco Pilots & Assistant Loco Pilots. Courses have been designed in collaboration with IRISSET.

14. The funds utilized on Kavach works so far up to Jun'26 is Rs. 3,875 Crores. The allocation of funds during the year 2026-27 is Rs. 2,066 Crores. Kavach work is going at good pace in the entire country. Requisite funds are made available as per the progress of works.
